BRUHAT BENGALURU MAHANAGARA PALIKE
YELAHANKA DIVISION

Name of Work:- Construction of CC Road and drain at Harohalli Village in Chowdeshwari ward no 02 of Yelahanka Sub Division

Estimate Cost: - Rs. 25.00 Lakhs

Executive Engineer

YELAHANKA Division, Bangalore

Scanned with CamScanner

Bruhat Bangalore Mahanagara Palike
Executive Engineer Yelahanka Division

Name of Work: Construction of CC road at Harohalli village in Chowdeshwari ward -02 of Yelahanka Sub division

								Estimate Cost	25.00 Lakhs
	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work . Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/Moorum.(Tipper 5.5 m3) (V-I.No 1.4,Page No-5 PWD SR 2021-22) & (V-III Page No.3, Item No.1.1 A of PWD SR 2021-22)								
	Basic Rate	186.00							
	Loading And Unloading	118.00							
	Sub Total	304.00							
	Area Weightage 10%	30.40							
	Total Rate	334.40							
	RCC Drain								
	Harohalli Village								
	Cross Rd-1	1	82.00	1.10	1.00	90.20			
						90.20	Cum	334.40	30,162.88
2	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) **Mix 1:3:6 (M10)** Using 40 mm nominal size graded crushed coarse aggregates (V-1, P.No-15, I No-2.1.3 of PWD SR								
	Basic Rate	5554.00							
	Area Weightage 10%	555.40							
	Total Rate	6109.40							
	RCC Drain								
	Harohalli Village								
	Cross Rd-1	1	82.00	1.10	0.15	13.53			
	CC Road								
	Harohalli Village								
	Cross Rd-1	1	83.00	5.00	0.15	62.25			
	Cross Rd-2	1	32.00	4.70	0.15	22.56			
	Cross Rd-3	1	25.00	5.30	0.15	19.88			
						118.22	Cum	6109.40	722222.72

Scanned with CamScanner

	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.(V-III, I.No 13.1 Page No 99, PWD SR 2021-22) (Issue rate on 07-07-22)								
	Basic Rate	92170.00							
	Area Weightage 10%	9217.00							
	Total Rate	101387.00							
	For RCC Drain, 60kg/Cum	1	25.83	60.00		1549.80			
						1549.80			
						1.55	Tn	101387.00	157129.57
4	Providing and laying in position **Reinforced cement concrete** for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) **M20 Design Mix Using 20 mm** nominal size graded crushed coarse aggregates (V-1,P.No.17, I.No.2.4.2 of PWD SR 2021-22) Apendx I, V-I P.No-115) (Issue rate on 07-07-22)								
	Basic Rate	5968.00							
	5% Centring	298.40							
	Sub Total	6266.40							
	Area Weightage 10%	626.64							
	Total Rate	6893.04							
	RCC Drain Raft								
	Harohalli Village								
	Cross Rd-1	1	82.00	0.90	0.15	11.07			
	RCC Drain Wall								
	Harohalli Village								
	Cross Rd-1	2	82.00	0.15	0.60	14.76			
						25.83	Cum	6893.04	178047.22
5	Providing and fixing precast reinforced cement concrete **covering slabs of 10Cm thick** made of M25 with OPC cement,@340kgs/cum with 20mm and down size graded granite metal coarse aggregate @0.70cum and fine aggregate & 0.74 cum with superplasticizer machine,mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work.(Exclusive of GST and Area Loading Charges)								
	Basic Data Rate	2072.00							
	Drain Top Covering Slab								
	Harohalli Village								
	Cross Rd-1	1	82.00	0.90		73.80			
	Missing/Damage Slabs	50	0.60	0.90		27.00			
						100.80	Sqm	2072.00	208857.60

Scanned with CamScanner

	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Earth work in surface excavation by **mechanical means** for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work ((V-I, P.No-8, I No-1.12 of PWD SR 2021-22)								
	Basic Rate	**65.00**							
	Area Weightage 10%	**6.50**							
	Total Rate	**71.50**							
	CC Road								
	Harohalli Village								
	Cross Rd-1	1	83.00	5.00	0.30	124.50			
	Cross Rd-2	1	32.00	4.70	0.30	45.12			
	Cross Rd-3	1	25.00	5.30	0.25	33.13			
						202.75	**Cum**	**71.50**	**14,496.27**
7	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 **M30 (Grade)**, coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete. as per the directions of the Engineer-in-charge of the work.(V-III, P.No-138,I No-20.29, KPWD SR 2021-22). (Issue rate on 07-07-22)								
	Basic Rate	**6512.00**							
	Area Weightage 10%	**651.20**							
	Total Rate	**7163.20**							
	CC Road								
	Harohalli Village								
	Cross Rd-1	1	83.00	5.00	0.15	62.25			
	Cross Rd-2	1	32.00	4.70	0.15	22.56			
	Cross Rd-3	1	25.00	5.30	0.15	19.88			
						104.69	**Cum**	**7163.20**	**749879.59**
8	**Cost of Haulage Excluding Loading** and Unloading Taking output 10 t load and lead 10 km = 100 t.km(V-III Page No.3, Item No.1.4A of PWD SR 2021-22)								
	Basic Rate	**12.00**							
	8KM Lead = 12*8	**96.00**							
	Area Weightage 10%	**9.60**							
	Total Rate	**105.60**							
	Qty frm Item No-1		90.2	1.28		115.46			
	Qty frm Item No-7		202.7	2.10		425.76			
						541.22	**t.Km**	**105.60**	**57,152.88**

Scanned with CamScanner

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
							Total Construction Cost	2117948.74
							18% GST for Construction Cost	381230.77
							Sub Total	2499179.51
							Utility Shifting,Miscellaneous and Rounding off	820.49
							GRAND TOTAL	2500000.00

Certificate

1. The workspot was inspected and works is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike limits.
3. The rates adopted based on the PWD SR,Bangalore circle for year 2021-2022, issue rates dated 07-07-2022 and Data Rates

Assistant Engineer
Ward No-02
BBMP Bangalore

Asst. Executive Engineer,
Yelahanka Sub Division
BBMP Bangalore

Executive Engineer,
Yelahanka Division
BBMP Bangalore

Administrative Approval

Accorded For 25.00 Lakhs.
Head of A/C P-3726
CER NO :53 Dt:22/8/2022

TA

CE (YNK)

Technical Sanction

Accorded For 25.00 Lakhs
Head of A/C P-3726
CER NO :72 Dt:22/8/2022

Scanned with CamScanner